# BRUHAT BANGALORE MAHANAGARA PALIKE

## SCHEDULE - B

**Name of work: Estimate for Improvements to Roads and Drains at Kempegowdanagara Colony in Ward No. 09, Vidyaranyapura Sub Division.**

| Sl. No. | Approved Qty. | Description | Unit | Schedule-B Rates | | |
|---|---|---|---|---|---|---|
| | | | | KRIDL | | |
| | | | | In Figures | Amount | In Words |
| 1 | **157.20** | KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. | cum | 81.62 | 12830.66 | Rupees Eighty One and Sixty Two Paise Only |
| 2 | **117.90** | KSRB 4-1.3 : Providing and laying in position plain cement concrete of **mix 1:4:8 with OPC cement @ 180 kgs with 40mm** and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. | cum | 4976.70 | 586752.93 | Rupees Four Thousand Nine Hundred Seventy Six and Seventy Paise Only |
| 3 | **98.25** | Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams. | cum | 6332.04 | 622122.93 | Rupees Six Thousand Three Hundred Thirty Two and Four Paise Only |
| 4 | **786.00** | Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc., with all lead and lift | sqm | 97.20 | 76399.20 | Rupees Ninety Seven and Twenty Paise Only |
| 5 | **78.00** | Providing **groove cutting** for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator and HOM of machinery including cost of blade coolant etc including cleaning of groove and providing sand and hot bitumne fillars, and filler metal etc., indluding cost of converyance of all materials, labours, lead and lift charges and all other incidental charges as per drawing and as per specification **Concrete Pavement** | rmt | 124.20 | 9687.60 | Rupees One Hundred Twenty Four and Twenty Paise Only |
| 6 | **149.34** | Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km | cum | 100.08 | 14945.95 | Rupees One Hundred and Eight Paise Only |
| | | Total | | | 1322739.27 | |

Signature of the Cont...

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

5/8/16